

**ACRIP FY 2024 ANNUAL PAVING - VARIOUS CITY STREETS
ALEXANDER CITY, AL
BID SHEET**

ITEM NO.	DESCRIPTION	UNIT	PLAN QUANTITY	UNIT PRICE	SUBTOTAL
1	BITUMINOUS TREATMENT "G"	SQUARE YARD	128,683		
2	PLANING EXISTING PAVEMENT (APPROX 1.10" THRU 2.0" THICK)	SQUARE YARD	38,294		
3	SUPERPAVE BITUMINOUS CONCRETE WEARING SURFACE LAYER, 3/8" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE A/B (APPROXIMATELY 165 LB/SY)	TONS	12,745		
4	SUPERPAVE BITUMINOUS CONCRETE WEARING LAYER, THIN LIFT MIX, ESAL RANGE A/B (APPROXIMATELY 100 LB/SY)	TONS	2,844		
5	SUPERPAVE BITUMINOUS CONCRETE UPPER BINDER LAYER, PATCHING, 1" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE A/B	TONS	400		
6	SUPERPAVE BITUMINOUS CONCRETE UPPER BINDER LAYER, LEVELING, 3/8" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE A/B	TONS	900		
7	MOBILIZATION	LUMP SUM	1		
8	SOLID YELLOW, CLASS 2, TYPE A TRAFFIC STRIPE	MILE	13.42		
9	SOLID TEMPORARY TRAFFIC STRIPE	MILE	13.42		
10	TRAFFIC CONTROL MARKINGS, CLASS 2, TYPE A	SQUARE FEET	2,764		
11	TEMPORARY TRAFFIC CONTROL MARKINGS	SQUARE FEET	1,704		
12	TRAFFIC CONTROL SCHEME	LUMP SUM	1		
				TOTAL:	

CONTRACTOR: _____

REPRESENTATIVES SIGNATURE: _____